

Oprawa oświetleniowa

Lighting Fixture

MONTAŻ

Przed przystąpieniem do montażu zapoznaj się z instrukcją. Montaż powinna wykonać osoba posiadająca odpowiednie uprawnienia. Wszelkie czynności wykonywać przy odłączonym zasilaniu. Przed pierwszym użyciem należy upewnić się co do prawidłowego mocowania mechanicznego i podłączenia elektrycznego. Przewody przyłączeniowe należy poprowadzić w taki sposób, aby uniemożliwić ich zetknięcie z nagrzewającymi się częściami wyrobu. Wyrobu nie użytkować w miejscu, w którym panują niekorzystne warunki otoczenia np. kurz, pył, woda, wilgoć wibracje itp.

EKSPLOATACJA / KONSERWACJA

Czyścić wyłączenie delikatnymi i suchymi tkaninami. Nie używać chemicznych środków czyszczących. Wyrób może nagrzewać się. Nie zakrywać wyrobu. Zapewnić swobodny dostęp powietrza. Regulację kierunku świecenia i/lub wymianę źródła światła należy wykonać po wystygnięciu wyrobu. Zaleca się kontrolę stanu wszystkich połączeń i elementów systemu oświetleniowego.

INSTALLATION

Read the instructions before installing. The installation should be carried out by a person with appropriate qualifications. All operations must be performed with the disconnected power. Be especially careful. Before first use, make sure that the mechanical fastening and electrical connection are correct. The connection cables should be routed in such a way as to prevent them from coming into contact with the heating parts of the product. Do not use the product in a place where unfavourable environmental conditions prevail, e.g. dust, water, moisture vibrations, etc.

OPERATION / MAINTENANCE

Maintenance should be carried out with power disconnected. Clean off with delicate and dry fabrics. Do not use chemical cleaners. The product should be supplied only with the rated voltage or the range of given voltages. The product may heat up to elevated temperatures. Do not cover the product. Ensure free access of air. Adjustment of the light direction and / or replacement of the light source should be made after the product has cooled down. It is recommended to check the status of all connections and components of the lighting system.

